

OSSERVAZIONI RELATIVE ALLO SVOLGIMENTO DEL SEMINARIO “DEPOSITO NAZIONALE” DA PARTE DEL RELATORE CORRADO ETTORE CIGOLINI

SOGIN SpA Prot. n. 0002163 del 14/01/2022

Considerazioni Generali

L'organizzazione di un Seminario Nazionale nell'ambito della procedura legata alla Carta Nazionale delle Aree Potenzialmente Idonee (CNAPI) destinate ad ospitare il “**Deposito Nazionale dei Rifiuti Radioattivi e Parco Tecnologico**” è normato dal art. 27 del D.l.s n. 31/2010 ed è stata attivata nell'ambito della “Consultazione pubblica” che ha coinvolto i diversi portatori di interesse, incluse le persone fisiche.

La procedura citata identifica Sogin S.P.A. come soggetto responsabile della individuazione, realizzazione ed esercizio del Deposito Nazionale destinato ad ospitare i rifiuti radioattivi a bassa e media attività e del “connesso” Parco Tecnologico. La procedura portata avanti da Sogin S.P.A. ha tenuto conto dei criteri previsti nella Guida Tecnica n. 29 dell'Istituto Superiore per la Protezione e la Ricerca Ambientale (ISPRA) ed ha redatto la Carta Nazionale delle Aree Potenzialmente Idonee (CNAPI). Relativamente alla medesima, gli enti locali e i diversi portatori di interessi hanno espresso le loro osservazioni (entro il 5 Luglio del 2021). Successivamente Sogin ha attivato l'organizzazione del così detto “Seminario Nazionale”. **Nonostante le conclamate intenzioni di Sogin di coinvolgere attivamente i portatori di interesse ed i territori, la realizzazione del Seminario ha presentato una serie di criticità che hanno di fatto inibito la comunicazione e la discussione tra i convenuti, la trasparenza delle scelte tecnologiche e programmatiche e soprattutto l'analisi, anche in contraddittorio, dell'idoneità dei singoli siti CNAPI.** Il seminario si è praticamente risolto come una successione di “monologhi”, spesso discontinui e sconnessi dal punto di vista tematico, dove i partecipanti hanno dovuto “riassumere” in 10 minuti e 5 diapositive i risultati ottenuti, attraverso approfonditi studi tecnico-scientifici e giuridici, le loro osservazioni inviate a Sogin nell'estate del 2021 (e anche successivamente: ad esempio, relativamente all'area TO-10, i Comuni di Rondissone e Mazzè hanno prodotto nuove e rilevanti integrazioni alle loro osservazioni iniziali in data 30 Settembre 2021, mentre quelle del primo comune sono state riportate nel dominio “Documenti Seminario Nazionale”, quelle del Comune di Mazzè non sono state pubblicate, ed entrambe non risultano tuttora incluse nella sessione del sito “Osservazioni e Proposte Tecniche Trasmesse”. Tutto ciò ha reso e rende complesso e macchinoso l'accesso ai recenti sviluppi tecnici e giuridici in ambito CNAPI).

Nondimeno critica risulta la stesura degli Atti di Restituzione Lavori operata da Sogin, reperibile al sito https://www.depositonazionale.it/seminario_nazionale_documenti/atti-conclusivi-seminario-nazionale.pdf,

dove la “Trascrizione degli Interventi” dei portatori di interessi è stata sistematicamente ridimensionata mentre quella dei tecnici Sogin è stata riprodotta integralmente (cfr. Sessione Piemonte del 16 Novembre 2021).

OSSERVAZIONI SPECIFICHE

Entrando nel merito dell'organizzazione del Seminario da parte di Sogin SPA è importante segnalare che, oltre alla partecipazione dei soggetti portatori di interesse (Regione, Città Metropolitana, Comuni, Enti, Atenei, Associazioni, Comitati e singole persone fisiche) presenti sui territori interessati, Sogin SPA ha coinvolto una serie di tecnici, sia interni che esterni a Sogin medesima, che sono stati “invitati” a partecipare ai lavori del seminario. Nelle singole sessioni regionali, sia i portatori di interesse che gli esperti avevano a disposizione 10 minuti per ogni singolo intervento. Tuttavia **gli Atti di Restituzione prodotti da Sogin** relativi alla sessione Piemonte del 16 Novembre 2021 (cfr. SemNaz__RestituzioneLavori_SESSIONE_PIEMONTE.PDF reperibile al sito https://www.seminariodepositonazionale.it/wp-content/uploads/2021/08/SemNaz__RestituzioneLavori_SESSIONE_PIEMONTE.pdf) **riportano una “sintesi” di 1300-1700 caratteri per i singoli interventi dei portatori di interesse, mentre per gli esperti invitati da Sogin sono rilevabili due interventi di 5173 caratteri (Dott. Michele Rosati) e 4423 caratteri (Ing. Stefania Uras). Il confronto tra la trascrizione di questi interventi ed i video riportati dimostra che, in questi casi, risulta fedele ed integrale. Ben diverso è il risultato relativo alla trascrizione degli interventi dei portatori di interesse. Nel mio caso specifico (come persona fisica) si conteggiano 1350 caratteri, mentre la trascrizione integrale da me operata, sulla base della registrazione video, i caratteri risultano 6434. Si deduce quindi che la “sintesi” di Sogin è stata radicale, direzionale e discriminatoria in quanto l'Atto di Restituzione riporta circa il 21% di quanto effettivamente comunicato. Si tratta quindi del “Riassunto della Sintesi” che rappresenta un'erronea, frammentaria ed insufficiente semplificazione di quanto effettivamente esposto.** Infatti detto testo presenta una serie di errori, lacune ed omissioni come evidenziato nella mia nota PEC del 14 Dicembre 2021 indirizzata a Sogin in cui si richiedeva la correzione/sostituzione della Restituzione dell'intervento riportato agli atti:

cosa che purtroppo non è avvenuta. Nella parte a seguito si riportano dettagliatamente le criticità rilevate.

Analisi della Restituzione Lavori operata da Sogin SPA

I° Intervento (a 11'30" dall'inizio sessione). Restituzione Lavori contenuta da pag. 49 a pag. 50 degli Atti Sogin.

Restituzione Sogin, pag 49 linee 23-25 (dall'alto): "Ha illustrato elementi geomorfologici del territorio TO10, in particolare in riferimento al profilo sismico del territorio".

Replica del Relatore. Segnalazione Errore: A inizio presentazione non sono stati illustrati gli elementi "geomorfologici" del territorio bensì quelli tettonici, strutturali e geofisici della regione.

L'errore è macroscopico e concettuale, evidenziato dalla frase successiva che cita "in riferimento al profilo sismico del territorio". La geomorfologia infatti è una disciplina delle scienze della terra che si occupa della "morfologia" della superficie terrestre nettamente distinta dalla sismica (che è parte della geofisica).

Replica del Relatore. Segnalazione lacuna e/o omissione: Nella restituzione operata da Sogin non vengono descritti i rapporti strutturali tra le unità alpine retrovergenti e i fagliamenti (sovrascorrimenti) appenninici di cui uno di quest'ultimi è direttamente sottostante all'area TO-10 (vedasi il profilo CROP-ALP 1 Diapositiva 6 della presentazione). Vedasi Trascrizione Integrale dell'Intervento effettuata dal sottoscritto (in Allegato, cfr. i contenuti riportati dalla riga n. 11 alla riga 21).

Restituzione Sogin, pag 49 linee 29-30 (dall'alto): "Ha aggiunto che questa configurazione non soddisfa il CE3".

Replica del Relatore. Segnalazione Errore: ERRATO INVECE LO SODDISFA. Infatti nella trascrizione integrale dell'intervento, e nell'audio della ripresa del medesimo (cfr. dal minuto 14'42" al minuto 14'53" dall'inizio della registrazione video della sessione), si rileva la seguente affermazione: "Pertanto questa configurazione soddisfa il Criterio di Esclusione CE3, area interessata da fenomeni di fagliazione".

Restituzione Sogin, pag 50 linee 2-3 (dall'alto): “Ha poi presentato la sintesi delle accelerazioni orizzontali di picco come riportati dal DN GS 005 di Sogin”.

Replica del Relatore. Segnalazione Errori; il primo di trascrizione il secondo concettuale.

Errore n. 1. Il documento erroneamente citato (DN GS 005) è in realtà il DN GS 00095. Infatti alle righe 46-49 della mia Trascrizione Integrale dell'Intervento si riporta: “In questa prospettiva ben s'inquadra il rapporto DN-GS-00095 “Valutazione della sismicità del territorio italiano. Relazione finale” commissionato dalla Sogin al Dipartimento di Scienze della Terra dell'Università Sapienza di Roma”.

Errore n. 2. Il documento DN GS 00095 non riporta il valore delle accelerazioni orizzontali di picco nel quadrante considerato. Queste sono state calcolate sulla base del “modello geofisico” proposto dal citato studio DN GS 00095 che riporta le “Mappe della Magnitudo massima attesa su base geologica e geofisica” dei terremoti della regione.

Infatti la Trascrizione Integrale dell'Intervento effettuata dal sottoscritto riporta (righe 49-59): “Il modello geofisico elaborato ha permesso di ottenere le “Mappe della Magnitudo massima attesa su base geologica e geofisica” di terremoti, ripartita per i singoli quadranti di 25 x 25 km. Il documento citato indica che la magnitudo massima attesa per il settore TO-10 possa teoricamente arrivare a Magnitudo di 6.5-6.7, lungo faglie con estensioni di 24-30 km, associate a dislocazioni di 5-10 km. Queste sono le Magnitudo caratteristiche di alcuni terremoti storici del dominio padano.

Inoltre la presenza di un “Gap Sismico”, evidenziato a destra indica che questo settore viene considerato ad “alto rischio sismico” in quanto l'energia sismica non viene regolarmente dissipata come nelle altre zone limitrofe, caratterizzate quest'ultime da una maggior sismicità. Pertanto l'accumulo della deformazione elastica può favorire la rottura di porzioni significative di crosta ed innescare terremoti di magnitudo considerevole con valori di accelerazioni orizzontali di picco ben superiori a 0,25”.

Replica del Relatore. Segnalazione omissione: Non viene riportato il valore delle accelerazioni di picco ottenute, che è superiore a 0,25 g e che soddisfa il Criterio di Esclusione CE 2: aree contrassegnate da sismicità elevata (i valori sono chiaramente visibili nella Tabella riportata alla Diapositiva 6 della presentazione). Tale valore (0,25 g) è quello che caratterizza il limite inferiore (ovvero che non può essere superato) del Criterio di Esclusione CE2 della Guida ISPRA n. 29 che è un elemento significativo e portante di tutta la presentazione. Vedasi Trascrizione Integrale dell'Intervento effettuata dal sottoscritto che riporta (alle righe 56-60) “Pertanto l'accumulo della

deformazione elastica può favorire la rottura di porzioni significative di crosta ed innescare terremoti di magnitudo considerevole con valori di accelerazioni orizzontali di picco ben superiori a 0,25.

Quindi l'area TO-10 rientra nel criterio CE2 aree contrassegnate da sismicità elevata”.

Restituzione Sogin, pag. 50 linee 3-10 (dall'alto): Ha quindi sottolineato che l'area è caratterizzata da un elevato grado di sismicità potenziale, ricadendo in una zona di Gap Sismico con associato sollevamento tettonico attivo, dimostrato anche dall'esistenza di “entrenched meanders” e dati archeologici.

Replica del Relatore. Segnalazione omissione: *Non si citano “i grandi terremoti padani” ovvero quelli relativi terremoto di Verona del 1117, di Brescia del 1222, del Friuli del 1976 e dell'Emilia del 2012 (cfr. Trascrizione Integrale dell'Intervento, righe 88-89)*

FINE PRIMO INTERVENTO

14/01/2022

1 **Trascrizione Integrale dell'intervento effettuata da parte del Relatore:**

2 **Corrado Ettore Cigolini**

3
4 **Intervento al Seminario Deposito Nazionale del 16 Novembre 2021,**

5 **Sessione Piemonte AREA TO-10.**

6
7 **I° Intervento di Corrado Ettore CIGOLINI (a 11'30" dall'inizio sessione)**

8 Buongiorno,

9 **DIPOSITIVA**

10 I dati scientifici qui presentati sono stati pubblicati sulla rivista scientifica internazionale LAND.

11 Nella Figura estratta dal Modello Strutturale d'Italia si riportano le principali unità tettoniche
12 presenti a scala regionale che evidenziano il fronte appenninico giustapposto alle falde
13 retrovergenti alpine in corrispondenza della così detta Avanfossa Padana. I sovrascorrimenti
14 appenninici vengono considerati come faglie composite e capaci (vedasi dati DISS, ITHACA,
15 GNDT). A Nord dei medesimi si ritrova la sinclinale di Saluggia che borda la collina Torinese e del
16 Monferrato. Più a Nord si rilevano dei sistemi di pieghe anticlinale-sinclinale e sinclinale-
17 anticlinale. Nella figura viene indicata la traccia del profilo sismico CROP-ALP 1 lungo
18 l'allineamento Castellamonte-Lamporo che attraversa l'area TO-10. A destra viene rappresentata
19 l'interpretazione della sezione sismica dal bacino di Savigliano attraverso la collina torinese fino a
20 San Benigno, riportata nel *Documento Sogin DN-GS-00223*. Nell'ovale si può notare il fagliamento
21 crostale tra le unità appenniniche e quelle alpine, che raggiunge i 10 km di profondità.

22
23 **DIPOSITIVA**

24 Nel riquadro a sinistra viene evidenziata la traccia sismica attraverso le Alpi Occidentali.
25 Il profilo sismico permette di identificare discontinuità profonde quali variazioni della geometria
26 degli strati, faglie e piegamenti. In particolare, nella parte superiore della figura vengono riportate le
27 tracce sismiche acquisite strumentalmente, mentre in quella sottostante viene riportata
28 l'interpretazione geologico-strutturale e stratigrafica. In particolare si evidenzia la presenza di una
29 faglia frontale appenninica, di tipo thrust fault, che disloca le unità terziarie e quaternarie fino ad
30 interessare le rocce del basamento sudalpino, a circa 8 km di profondità. Questa struttura è la
31 continuazione, verso Est, del fagliamento crostale rilevato a Sud di San Benigno. Quindi è pluri-
32 chilometrica come struttura.

33 Ciò dimostra la presenza di una tettonica attiva dove riscontriamo di una serie di pieghe che
34 deformano le unità Plio-Quaternarie e sono rappresentate nel riquadro interno. L'azione combinata
35 di questi processi di fagliazione-piegamento-sollevamento determinano un alto rischio
36 sismogenetico.

37 Pertanto questa configurazione soddisfa il Criterio di Esclusione CE3, area interessata da fenomeni
38 di fagliazione.

39
40 **DIPOSITIVA**

41 Il criterio CE2 della Guida Tecnica n. 29 di ISPRA prevede l'esclusione delle aree "contrassegnate
42 da sismicità elevata" ed utilizza come riferimento le Norme Tecniche per le Costruzioni nonché le
43 Mappe di Pericolosità Sismica dell'INGV. Il medesimo prevede che la "sismicità elevata" venga
44 contrassegnata per valori di picco di "accelerazione al substrato rigido", per un tempo di ritorno di
45 2475 anni. Tali riferimenti sono, dal punto di vista temporale, estremamente limitativi per ciò che

46 concerne i processi geologici ed in particolare quelli tettonici. In questa prospettiva ben s'inquadra
47 il rapporto DN-GS-00095 "Valutazione della sismicità del territorio italiano. Relazione finale"
48 commissionato dalla Sogin al Dipartimento di Scienze della Terra dell'Università Sapienza di
49 Roma. Il modello geofisico elaborato ha permesso di ottenere le "Mappe della Magnitudo massima
50 attesa su base geologica e geofisica" di terremoti, ripartita per i singoli quadranti di 25 x 25 km. Il
51 documento citato indica che la magnitudo massima attesa per il settore TO-10 possa teoricamente
52 arrivare a Magnitudo di 6.5-6.7, lungo faglie con estensioni di 24-30 km, associate a dislocazioni di
53 5-10 km. Queste sono le Magnitudo caratteristiche di alcuni terremoti storici del dominio padano.
54 Inoltre la presenza di un "Gap Sismico", evidenziato a destra indica che questo settore viene
55 considerato ad "alto rischio sismico" in quanto l'energia sismica non viene regolarmente dissipata
56 come nelle altre zone limitrofe, caratterizzate quest'ultime da una maggior sismicità. Pertanto
57 l'accumulo della deformazione elastica può favorire la rottura di porzioni significative di crosta ed
58 innescare terremoti di magnitudo considerevole con valori di accelerazioni orizzontali di picco ben
59 superiori a 0,25.

60 Quindi l'area TO-10 rientra nel criterio CE2 aree contrassegnate da sismicità elevata.

61

62 **DIAPPOSITIVA**

63

64 Inoltre, dati ottenuti da un'analisi della letteratura dimostrano che l'area TO-10 ricade in una zona
65 di sollevamento tettonico attivo. Nell'immagine a sinistra vengono riportati i dati SqueeSAR della
66 Regione Piemonte e relativa legenda. Questi dati mostrano un sollevamento di 1-3 (mm/a) lungo il
67 Po sul fronte del Chivassese-Monferrato (linea verde), più a nord si rileva un analogo sollevamento
68 1-3 (mm/a) tra Montanaro e Rondissone e Caluso-Mazzè (linee blu). Le linee rosse evidenziano un
69 processo di deflazione legate all'emungimento d'acqua per uso agricolo nell'area TO-10. I dati di
70 sollevamento sono in perfetto accordo con quelli ottenuti dalle livellazioni topografiche eseguite
71 periodicamente nell'arco di 50 anni (Figura a destra) che si attestano a circa 1.5 mm/a a Sud
72 dell'arco morenico.

73 Infine nell'immagine centrale viene riportata la Proiezione equiareale sul reticolo di Smidth relativa
74 all'orientamento lineare di danneggiamenti nei ciottoli e blocchi di ghiaie consolidate a circa 10 m
75 di profondità dal p.c.. Si evince un orientamento compressivo con direzione NS.

76 Il sollevamento tettonico dell'area e la dinamica compressiva registrata comprovano ulteriormente
77 che i criteri CE2 e CE3 risultano soddisfatti.

78

79 **DIAPPOSITIVA**

80

81 Si riporta la sintesi delle accelerazioni orizzontali di picco ottenute per le magnitudo del modello
82 DN GS 00095 ad una distanza epicentrale di 5 km (in accordo con la presenza del predetto
83 fagliamento attivo). I valori superano abbondantemente quelli di 0,25 g normati dal CE2 per un
84 suolo di tipo A.

85 Contrariamente a quanto ritenuto da SOGIN, l'area è caratterizzata da un elevato grado di sismicità
86 potenziale, ricadendo in una zona di Gap Sismico con associato sollevamento tettonico attivo.
87 Questa configurazione ricalca gli assetti tettonici associati ai forti terremoti padani legati alla
88 interazione tra il margine retrovergente alpino e quello appenninico (e.g., terremoto di Verona del
89 1117, di Brescia del 1222, del Friuli del 1976 e dell'Emilia del 2012).

90 Contrariamente a quanto ritenuto da SOGIN, l'area è interessata da evidenti e macroscopici
91 fenomeni di fagliazione attiva.

92

93 **Grazie per l'attenzione**

94 **FINE PRIMO INTERVENTO**

95

RE:Errori di trascrizione e lacune contenuti negli Atti relativi Seminario Deposito Nazionale “Restituzione Lavori” (SemNaz__RestituzioneLavori_SESSIONE_Piemonte.pdf) relativi ai miei interventi nell’ambito della “Sessione Piemonte” del 16 Novembre 2021.

Da corrado.cigolini@pec.it <corrado.cigolini@pec.it>
A consultazionepubblica@pec.depositonazionale.it
<consultazionepubblica@pec.depositonazionale.it>, sogin@pec.sogin.it
<sogin@pec.sogin.it>
Cc comune.mazze@postecert.it <comune.mazze@postecert.it>,
comune.rondissone.pec@actaliscertymail.it
<comune.rondissone.pec@actaliscertymail.it>, protocollo@pec.comune.caluso.to.it
<protocollo@pec.comune.caluso.to.it>, a.zavattaro@awn.it <a.zavattaro@awn.it>
Data martedì 14 dicembre 2021 - 16:22

Sogin SPA

sogin@pec.sogin.it

consultazionepubblica@pec.depositonazionale.it

P.C. Arch. A. Zavattaro; Presidente Comitato “Io mi Rifiuto”: a.zavattaro@awn.it

Al Sindaco del Comune di Mazzè: comune.mazze@postecert.it

Al sindaco del Comune di Rondissone: comune.rondissone.pec@actaliscertymail.it

Alla Sindaca del Comune di Caluso: protocollo@pec.comune.caluso.to.it

RACCOMANDATA VIA PEC

OGGETTO: Errori di trascrizione e lacune contenuti negli Atti relativi Seminario Deposito Nazionale “Restituzione Lavori” (SemNaz__RestituzioneLavori_SESSIONE_Piemonte.pdf) relativi ai miei interventi nell’ambito della “Sessione Piemonte” del 16 Novembre 2021. Trasmissione trascrizione integrale degli interventi e richiesta di correzione e/o sostituzione delle parti relative alla “restituzione” delle mie presentazioni.

Spett.le Sogin SPA,

con riferimento a quanto in oggetto si prende atto del volume di lavoro prodotto nell’ambito della stesura degli Atti di Restituzione dei lavori del Seminario Deposito Nazionale. **Tuttavia devo segnalare di aver incontrato diversi errori di trascrizione e lacune relativi ai miei interventi. Mentre i primi pur essendo formali risultano comunque sostanziali, le seconde precludono l’oggettiva comprensione delle affermazioni prodotte durante gli interventi medesimi. Ne deriva un quadro approssimativo e fuorviante di quanto comunicato nella Sessione, verificabile inequivocabilmente attraverso l’analisi della**

registrazione degli interventi.

Colgo l'occasione per esprimere le mie perplessità legate al fatto che nessuna comunicazione scritta è inoltrata ai partecipanti e portatori di interesse invitandoli a verificare il documento in oggetto. Copia della presente viene estesa ai sindaci dei Comuni coinvolti in area CNAPI TO-10 ed al Presidente del Comitato per la Salvaguardia del Territorio Chivassese-Canavesano "Io mi rifiuto" (che mi ha delegato per la seconda presentazione).

Si richiede pertanto **un'adeguata correzione e/o sostituzione delle parti relative alla "restituzione" delle mie presentazioni sulla base della trascrizione integrale delle medesime riportata nell'allegato alla presente.**

Distinti saluti,

Corrado E. Cigolini

Allegato Correzioni a Restituzione Lavori_Cigolini.pdf

RE:Errori di trascrizione e lacune contenuti negli Atti relativi Seminario Deposito Nazionale “Restituzione Lavori” (SemNaz__RestituzioneLavori_SESSIONE_Piemonte.pdf) relativi ai miei interventi nell’ambito della “Sessione Piemonte” del 16 Novembre 2021.

Da Posta Certificata Legalmail <posta-certificata@legalmail.it>

A corrado.cigolini@pec.it <corrado.cigolini@pec.it>

Data martedì 14 dicembre 2021 - 16:22

Ricevuta di avvenuta consegna

Il giorno 14/12/2021 alle ore 16:22:14 (+0100) il messaggio "RE:Errori di trascrizione e lacune contenuti negli Atti relativi Seminario Deposito Nazionale “Restituzione Lavori” (SemNaz__RestituzioneLavori_SESSIONE_Piemonte.pdf) relativi ai miei interventi nell’ambito della “Sessione Piemonte” del 16 Novembre 2021." proveniente da "corrado.cigolini@pec.it" ed indirizzato a "consultazionepubblica@pec.depositonazionale.it" è stato consegnato nella casella di destinazione.

Questa ricevuta, per Sua garanzia, è firmata digitalmente e la preghiamo di conservarla come attestato della consegna del messaggio alla casella destinataria.

Identificativo messaggio: opec296.20211214162211.09655.255.2.67@pec.aruba.it

Delivery receipt

The message "RE:Errori di trascrizione e lacune contenuti negli Atti relativi Seminario Deposito Nazionale “Restituzione Lavori” (SemNaz__RestituzioneLavori_SESSIONE_Piemonte.pdf) relativi ai miei interventi nell’ambito della “Sessione Piemonte” del 16 Novembre 2021." sent by "corrado.cigolini@pec.it", on 14/12/2021 at 16:22:14 (+0100) and addressed to "consultazionepubblica@pec.depositonazionale.it", was delivered by the certified email system.

As a guarantee to you, this receipt is digitally signed. Please keep it as certificate of delivery to the specified mailbox.

Message ID: opec296.20211214162211.09655.255.2.67@pec.aruba.it

postacert.eml

dati-cert.xml

smime.p7s

Article

Locating the Italian Radioactive Waste Repository: Issues and Perplexities Arisen from Open Data-Based Analyses about the TO-10 Site (NW Italy)

Enrico Borgogno-Mondino ^{1,*} , Andrea Borgia ² and Corrado Cigolini ³¹ Department of Agriculture, Forest and Food Sciences, University of Torino, 10124 Torino, Italy² EDRA, 00134 Roma, Italy; andrea@borgia.net³ Department of Earth Sciences, University of Torino, 10124 Torino, Italy; corrado.cigolini@unito.it

* Correspondence: enrico.borgogno@unito.it

Abstract: Recently, Italy has started the procedure for the selection of suitable sites for hosting the National Repository for Low-Medium Activity Radioactive Wastes. Sogin spa, a public company, taking into account the criteria of the ISPRA Technical Guide no. 29, solicited by the EU Directive 2011/70/Euratom, has presented the CNAPI (National Map of the Potentially Suitable Areas) which has become operative since 5 January 2021. Sixty-seven sites were identified in Italy as potentially suitable for hosting the repository. Some criticalities immediately appeared concerning the properness of the selection. An analysis was, therefore, achieved to explore part of the rationales underlying the adopted procedure. A paradigmatic site, namely the TO-10 one (NW Italy), was chosen for the analysis, which highlighted significant anomalies affecting both the procedure rationales and its results. Since the selection process majorly relies on geographical data, attention was particularly paid on the role of official data from open archives. With reference to the most updated and detailed ones, we demonstrated that the Sogin procedure suffers from several critical points. In particular, with reference to the TO-10 site, we found that it cannot be absolutely considered to be suitable for hosting the National Deposit. In fact, it proved to match several exclusion criteria included in the ISPRA Technical Guide n. 29. These include: the potentially high “seismic risk” due to a “seismic gap” and complex tectonics associated with uplift (up to 1–1.5 mm/y); a highly vulnerable and extremely superficial groundwater table; a high permeability (10^{-2} – 10^{-3} m/s) of the cover sedimentary units; not proper buffer zones around local settlements. In spite of the local specificity of the analysis, results concerning procedure weaknesses are general. Consequently, we expect that they can be a stimulus for Sogin to more properly face the next steps of the selection procedure.



Citation: Borgogno-Mondino, E.; Borgia, A.; Cigolini, C. Locating the Italian Radioactive Waste Repository: Issues and Perplexities Arisen from Open Data-Based Analyses about the TO-10 Site (NW Italy). *Land* **2021**, *10*, 932. <https://doi.org/10.3390/land10090932>

Academic Editor: Alex Lechner

Received: 16 July 2021

Accepted: 2 September 2021

Published: 5 September 2021

Keywords: CNAPI; open data; TO-10; radioactive waste; GIS; IAEA

Publisher's Note: MDPI stays neutral with regard to jurisdictional claims in published maps and institutional affiliations.



Copyright: © 2021 by the authors. Licensee MDPI, Basel, Switzerland. This article is an open access article distributed under the terms and conditions of the Creative Commons Attribution (CC BY) license (<https://creativecommons.org/licenses/by/4.0/>).

1. Introduction

Radiation and radioactive materials have many useful applications in different sectors, from energy production to medicine, industry, and agriculture. Risks related to radiation exposure of workers, the population, and the environment must be assessed and controlled, while production, transport, and use of radioactive wastes (RW) must be strictly regulated to guarantee safety. In particular, RW management and storage are some of the main challenges that the world must, and will have to, deal with in the many years to come. RW can be liquid, solid, or gaseous. They contain radionuclides at concentrations, or have activities, above the safety levels established by regulatory agencies [1–3]. From a political point of view, RW management is a critical issue; from a scientific point of view, proposed solutions still require further research for technical and safety improvements [4]. Many studies have been conducted throughout the world. Nevertheless the long-term environmental impacts of RW, particularly in presence of even small leakages, must still be fully assessed [5,6]. In fact, many parameters intervene during RW conditioning,

transport, and storage operations, possibly resulting in radionuclides migration to the environment [7]. Safety regulations are not always sufficient to avoid accidents, whose effects may exceed national boundaries. International cooperation is, therefore, essential to promote security at a global scale by sharing experience that can improve the ability to control radiation hazards, prevent emergencies, and mitigate consequences [8]. Diligence is due, at both the national and international level, in following proper protocols, detecting hazardous conditions and activating prompt interventions for both hazard reduction and remediation [9].

International RW safety standards have been established by the International Atomic Energy Agency (IAEA). IAEA defines standards for structures and procedures related to activities suffering from radiation hazard, including nuclear plants and RW management. In particular, it defines safety standards, requirements and measures to control human exposure to radiation and radioactive material releases into the environment, aiming at limiting the probability of catastrophic events [10,11]. According to IAEA guidelines [8], the procedure for locating RW repositories must follow four steps: (a) conceptualization and general site design; (b) potential sites selection; (c) potential sites characterization; and (d) final site selection. In practice, from several potential sites resulting from point (b), a more detailed selection follows—point (c)—based on the assessment of specific environmental and socio-political factors such as land use, transport infrastructure, demographic conditions, local economic activities, etc. It has to be considered that the process may involve different levels of public and local players and include the use of vetoes and volunteering.

Recently, Italy has started the procedure for the identification of suitable sites for hosting its national RW repository. Sogin spa (hereinafter called Sogin), a public company, has proposed a map (called CNAPI) locating 67 potential suitable areas to host the repository. Selection procedure by Sogin has taken into account the criteria as defined in the Technical Guide no. 29 [12] edited by the Italian Institute for Nuclear Safety and Radio Protection (ISPRA, presently ISIN). This was based on the above mentioned IAEA guidelines [8]. In [12] ISPRA has defined some criteria of “exclusion” (hereinafter called EC) and some others for technical specification of site features (hereinafter called “investigation criteria”, IC), both defining the requirements of potential sites all over the national territory. These criteria have been defined based on the following issues: (1) geological, geomorphological and hydraulic features of the area; (2) hydrogeological and chemical characteristics of the soil, to counteract the possible transfer of radionuclides into the biosphere; (3) protection and preservation of the territory and cultural heritage; (4) distance of the repository from man-made infrastructures and human activities; (5) distance from underground natural resources; and (6) protection from extreme weather conditions.

The present step of the selection workflow should correspond to the (b) point of the previously cited IAEA procedure. Nevertheless, Sogin has already anticipated a sorted list of suitable sites based on the adoption of a limited number of IC out of the many that were defined in [12]. Preliminary projects concerning RW deposit structure and the related technological park were also provided in [13].

It is worth remarking that EC and IC criteria can be associated to steps (b) and (c) of the IAEA procedure, respectively. It sounds clear that the inclusion of a certain criterion into the EC or IC group strongly affects the final solution of the decision process. In fact, while EC operate in a in/out mode by immediately including, or excluding, a given area, IC play a more understated role, being called to just grading the suitability of selected sites. This makes possible that, once a site is included among the candidates (not complying the EC criteria), the final choice may not exclusively obey to technical and scientific principles, but be possibly conditioned by economic and political dictates. Conveniently acting on the IC criteria—and related grading—permits, in fact, to introduce elements of subjectivity that could compromise a transparent solution.

ISIN/ISPRA guidelines strongly rely on the adoption of geographical data that represent the main tool for site selection [14–16], permitting them to spatially formalize both EC and IC criteria. It is worth stating that proper data (in terms of content, updating and

detail level) are basic to guarantee robust deductions. When a public player (such as Sogin) is called to achieve such an analysis, possibly granted through public money, it would be desirable that all the available open and free data were used, especially if obtainable from official and institutional subjects (regions, provinces and municipalities). This makes possible to save technical efforts and further spending of public money in the next phases of the procedure, when local communities, through their local administrations, have to eventually demonstrate unsuitability of their territories.

Unexpectedly, the Sogin procedure shows significant lacks in open data utilization. In fact, all spatial concerns are based on a very limited number of data, mainly having a homogeneous coverage over the Italian territory. No concern about the current availability of data from regional geoportals, better describing local conditions, is shown. In this work, to highlight this important criticality of the Sogin process, the TO-10 site was used as a paradigm. According to Sogin, it resulted compliant with no EC criterion, and, therefore, suitable to host the repository. Moreover, the TO-10 site is presently the first one appearing in the graded list contained in the Sogin published document [17]. In this work, we demonstrate that available public data would have been enough to exclude the TO-10 site from the candidate ones already in the present step. The same is expected for other sites presently included in the CNAPI, as well. Consequently, one can assume this analysis to be general and useful to improve results in the next steps of the procedure.

We advise that only some out of the ISIN criteria were taken into consideration in our analysis (see Section 2). In particular, those more strictly related to spatial analysis and, therefore, relying on the adoption of geographical data obtainable from official free archives/geoportals and literature.

To give a comprehensive description of these issues, we initially explored the general traits of the Sogin procedure, highlighting the most evident weaknesses and related threats. Then, focusing on the TO-10 site, a detailed analysis based on available open data, was achieved, testing the compliance of the site with the selected EC and IC criteria. Given the particular nature of the analysis, we preferred to integrate the Results and Discussion sections in a single one, making possible a more comprehensive interpretation of the analysis.

2. Materials and Methods

Some general and evident concerns have to be, initially, given about the Sogin procedure, this being the starting point of this work. When trying to figure out anomalies that can be recognized in a selection process, perspective has to be shifted to the proper point of view; this strictly depends on the degree of caution one wants to pay. It is worth reminding that caution has to be consistent with the impact that the forecasted structure/action potentially has. With these premises, authors detected that the philosophy supporting the Sogin procedure relies on an inappropriate complete confidence about human activities and artefacts (i.e., repository engineering). According to this vision, the repository is assumed as completely safe with zero probability assigned to internal failures, or external unpredictable threats, whose effects, however, can dramatically affect local population and environment [18]. Ordinary evaluation and sizing approaches of engineering appear to be reverted. In fact, EC and IC criteria, are more aimed at testing the degree of protection of the repository itself by eventual menaces from the external context, than at protecting local population and environment in case of failure/accident of the repository itself. Some evidences come from the application of the EC10 and IC8 criteria (groundwater issues) and EC12 criterion (topological constraints relating the repository and its neighbour settlements). As far as groundwater is concerned, tested conditions are only addressed at verifying if it could ever interact with the repository substructures, possibly degrading them. As far as settlements are concerned, the buffer zone is set to such a value (1 km for smaller municipalities) that can be just intended for preserving the repository from external solicitations and, not certainly, to preserve local population from the failure of a nuclear waste repository. Additionally, the air compartment is not taken into consideration

at all, since the underlying hypothesis is that nothing will never fail in the repository and no radioactive pollutant can be introduced in the air.

A second great criticality of the Sogin procedure concerns the consistency between expected outputs from the (b) step of the IAEA selection procedure (namely, “potential sites selection”) and the ones by Sogin. The IAEA (b) step has to generate a list of suitable sites for the repository by applying EC criteria. No grading is associated by IAEA at this procedural step. Conversely, sites grading is the expected output of the next procedural step (c), when IC criteria have to be applied. Unexpectedly, in [17], a sorted list of sites is given by Sogin relying on a classification based on only three IC criteria (namely, IC10, IC11, IC12) out of the 13 defined in [12]. Additionally, the same document explicitly goes back to two EC criteria—namely, EC11 and EC12. It is not clear the motivation that made these IC criteria more important than the other ones (some of them even more important), nor the reason why Sogin (c) step had to consider two EC. For example, the hydrogeology-related IC8, was not considered in the sorting step. We remind that IC8 was in charge of absorbing the most of concerns (i.e., groundwater level, recharge areas of aquifers, permeability, etc.) that the EC10 criterion unreasonably neglected in the previous step.

It is, however, a fact that the anticipation, within an official published document, of a sorted list of sites during a step of a procedure that is not called to define it, appears as a distortion of the transparent decisional process based on objective and independent analysis. This sounds furtherly strange when considering that Sogin defines its procedure as “participatory”.

A further criticality by Sogin concerns the type of data (in particular the geographical ones) that the procedure based some of its deductions on. Sogin, in fact, did not consider official regional geodatabases that are known to provide updated data at the proper spatial scale. Moreover, some data were obtained from external suppliers, possibly showing a lower degree of officialdom and, generally, a reduced, and not properly updated, content. A paradigmatic example comes from the application of the EC13 criterion, concerning the road/railroad network analysis. It was, in fact, based on the *DBPrior10K* dataset (a so called harmonized “patchwork” of regional official databases from CISIS) integrated with the Navteq (Nokia 2012) one.

But the most critical element coming from the public documents that were published, is contained in the ISPRA Technical Guide n. 30 [19], following the ISPRA Technical Guide n. 29 [12]. In [19] it is stated that the same repository, designed and located to host “low and medium activity” radioactive wastes, will also host, for a “long lasting”, but temporary, period (no time limit is given, nor ensured), “high activity” RW. This unreasonable choice appears to furtherly revert ordinary planning approaches, where caution and structure oversizing are, generally, the leading criteria to protect population and environment.

In this framework of evident native faults of the procedure, we finally decided to test a subset of ISIN EC and IC criteria, namely EC2, EC3, EC4, EC5, EC10, EC12, IC2, IC3, and IC8 (Table 1). In particular, we tested those being majorly compliant with authors’ research fields and majorly relying on geographical data. The aim was to investigate if, from a strictly technical point of view, results from Sogin were consistent with those obtainable using more appropriate data from open archives. As previously mentioned, the analysis focused on the TO-10 site, the first one reported in the sorted list of suitable sites unexpectedly published in [17].

2.1. Study Area

The TO-10 site is located in the eastern sector of the Torino Metropolitan district (Piemonte region, NW Italy) and involves the municipalities of Caluso, Mazzé, and Rondissone. These municipalities counts about 13,500 inhabitants, that can reach 40,500 if the close municipality of Chivasso is considered. According to CNAPI, the TO-10 site sizes about 5.15 km² (Figure 1). The area develops on the right side of the Dora Baltea river; it is located at about 7 km from the existing EUREX Sogin nuclear waste repository and treatment area (Saluggia), and at about 26 km from the dismissed “E. Fermi” nuclear plant

(Trino Vercellese). It is worth to remind that, both these sites must be “decommissioned” in the near future due the extreme hydrogeological vulnerability of the area [20].

Table 1. Codes and meaning of the ISPRA/ISIN EC and IC criteria as reported in [12]. This work focused on only some of them (namely EC2, EC3, EC4, EC5, EC10, EC12, IC2, IC3, and IC8) with reference to TO-10 site.

Codes	Description	Codes	Description
EC1	Areas with presence of active or quiescent volcanoes	EC9	Areas interested by morphogenetic karst processes or with presence of sinkholes
EC2	Areas with high seismic activity	EC10	Areas with near surface piezometric levels or with piezometric levels which could anyhow interfere with the foundation of the disposal facility
EC3	Areas interested by superficial faulting	EC11	Naturalistic areas, protected under the legislation in force; Protected natural areas
EC4	Areas characterized by geomorphological and/or hydraulic risk and/or hazard of any grade as well as river belts	EC12	Areas at a unsuitable distance from residential zones
EC5	Areas with holocene alluvial deposits	EC13	Areas within a distance of 1 km from highways, all principal suburban roads, and the main and complementary railway lines
EC6	Areas located above 700 m a.s.l.	EC14	Areas with known presence of underground resources
EC7	Areas characterized by an average slope greater than 10%	EC15	With industrial activities involving major accident hazards, dams and artificial hydraulic barriers, airports or operating military shooting ranges
EC8	Areas within 5 km from the current coast line or, if more distant, located under 20 m a.s.l.		
IC1	Presence of secondary volcanic activities	IC8	Hydrogeological parameters
IC2	Presence of significant vertical movements as a result of subsidence and uplift phenomena (tectonic and/or isostatic)	IC9	Chemical parameters of soil and groundwater
IC3	Geological-morphostructural setting and presence of lithotypes with vertical and lateral variation	IC10	Habitats, animal and plant species of conservation importance, as well as geosites
IC4	Presence of endorheic type river basins	IC11	Agricultural production of outstanding quality and places of archaeological and historical interest
IC5	Presence of accelerated erosion phenomena	IC12	Availability of primary transport infrastructures
IC6	Weather and climatic conditions	IC13	Presence of relevant or strategic critical infrastructures
IC7	Physical and mechanical parameters of the soil		




Figure 1. Location of the study area within the Piemonte Region and Italy (b). In (a) the administrative boundaries of the involved municipalities (Mazze, Caluso, Rondissone, Chivasso, Trino, Saluggia) are reported together with the TO-10 area. In blue, the Saluggia and Trino municipalities presently hosting radioactivity-related facilities. Reference system is WGS84 UTM 32N.

2.2. Geographical Data

The core focus of this work develops around the application of the selected EC and IC criteria based on available free and official data from public geoportals. With respect to the TO-10 site (but the same could be done for the other sites located in the Piemonte Region), geographical data from open archives of Table 2 were used to accomplish the analysis.

Table 2. Geographical data from open archives used for this work.

Data	Description
Regional DTM	Local topography was described according to the available Piemonte Region Digital Terrain Model (DTM). DTM is supplied in grid format and obtained from a LiDAR acquisition operated between 2009 and 2011. Grid step size is 5 m and it is classified as a level 4 DTM having a vertical precision of ± 0.3 m in ordinary areas and ± 0.6 m in the so called “reduced accuracy areas”, like forests and densely urbanized sites.
Geological Data, Active Tectonics, Seismicity	These data have been used to evaluate how the TO-10 area meets the requirements of the EC2, EC3, IC2 and IC3 criteria included in [12]. The main reference is the Structural Model of Italy (scale 1:500,000) published by CNR [21] and available through the “Società Geologica Italiana”. Other geological maps can also be consulted online and include the Geological Map of Piemonte Region (scale 1:250,000) and the Trino and East Torino Sheets of CARG Map at the scale 1:50,000 both available at https://www.isprambiente.gov.it/Media/carg/piemonte.html (accessed on 23 April 2021). Additional data on active tectonics and seismicity were obtained from INGV database (https://istituto.ingv.it/risorse-e-servizi/archivi-e-banche-dati.html , accessed on 13 May 2021). It offers a complete historical dataset about current seismicity (ISIDE), several seismic catalogues and the “database” of Italian faults (DISS, ITHACA, GNDT). Technical reports (commissioned by Sogin) of the University of Insubria [22] and La Sapienza University [23] were also used (https://www.depositonazionale.it/documenti/pagine/documenti-progetto-preliminare.aspx , accessed on 13 May 2021).
Hydrogeological Data	Data about superficial and underground hydrological parameters were obtained from the Piemonte Region geoportal (www.geoportale.piemonte.it , accessed 23 April 2021). In particular: (a) a point vector layer (W) locating wells for water supply (nominal scale 1:10,000, updated 2005); (b) a line vector layer (PH) mapping the underground water level—aquifer piezometric head (nominal scale 1:100,000, updated 2002, level spacing = 5 m); (c) a line vector layer (AF) mapping the aquifer floor altitude (nominal scale 1:50,000, updated 2016, level spacing = 5 m); (d) a polygonal vector layer (RS) mapping groundwater recharge system (nominal scale 1:250,000, updated 2016). (e) the map “Hydrogeology of the western Po Plain (Piedmont, NW Italy)” by De Luca et al. [24] reporting estimated permeability for sediments in the Po plain. (f) the “Hazard Map for Alluvial Risk in the Piemonte Region” [25]
Built areas/technological facilities and infrastructures	Two maps were compared during this work: (a) the ISTAT “Località Italiane” vector layer (Localita_11_WGS84.shp, hereinafter called LOC2011) and (b) the Regional BDTRE 2021 geodatabase (hereinafter called BDTRE2021). (a) is the one all the procedures from Sogin were based on. It was obtained georeferenced in the WGS84 UTM 32N reference system. Nominal spatial scale is heterogeneous over the Italian territory. It varies from a scale of 1:5000 (typically in urban areas) to a scale of 1:25,000 (mainly in areas with low, or very low, population density). It was obtained from the ISTAT data warehouse updated 2011; (b) is the built areas layer from the regional geodatabase. It is supplied updated November 2019 and its scale varies between 1:2000 and 1:10,000. Reference system is WGS84 UTM 32N. The following technological infrastructures were also considered: 1-powerline; 2-gas pipeline; 3-plant for biogas production. 1 and 3 were mapped according to the BDTRE2021 geodatabase; 2 was derived by vectorization from hardcopy documents supplied by local administrations.

2.3. Geological, Tectonic and Seismogenic Analysis of the Area

The proposed analysis relies on the re-interpretation of the CROP-ALPS 1 seismic reflection data from Roure et al. [26] integrated with considerations about active tectonics and seismicity based on the INGV databases. CROP-ALPS 1 (also known as ECORS-CROP) project focused on the deeper structure of the orogen in the French-Italian sector of Western Alps [26,27]. Nevertheless, in the SE sector, original data of the profile show a proper resolution for analysing superficial structures related to the Plio-Pleistocene coverings.

2.4. Seismic Hazard of the TO-10 Area

The EC2 criterion of the Technical Guide n. 29 [12] is intended to exclude those areas “marked by high seismicity”. It uses, as a reference, the Technical Standards for Constructions (Ministerial Decree 14 January 2008, [28]) and the INGV Seismic Hazard Map ([29], <http://esse1.mi.ingv.it/>, accessed on 13 May 2021). These documents indicate that “high seismicity” corresponds to peak values of “acceleration (PGA) at the rigid substrate equal to, or greater than, 0.25 g for an earthquake return time of 2475 years”.

Seismic Hazard Maps of Italy are determined on the basis of the known instrumental and historical seismicity that is reported in the Parametric Catalogues of Italian Earthquakes (see <http://emidius.mi.ingv.it/CPTI/>, [30], accessed on 13 May 2021) and in the Catalogue of Strong Earthquakes in Italy (<http://storing.ingv.it/cfti/cfti5/>, [31], accessed on 13 May 2021). In these catalogues, the “older” recorded earthquakes date back to 217 B.C. and 461 B.C., respectively, showing to be clearly incomplete for previous periods. Therefore, the EC2 exclusion criterion defined in [12] is in itself hard to be applied, given the limited information on earthquake dates and their correspondent magnitudes; in fact, the EC2 criterion explicitly refers to the events occurred in the 2475 years B.P., that were not recorded. Certainly, this deficiency is even more significant if one has to refer to the time-scale of geological processes. With these premises, interesting information come from the study conducted by the Department of Earth Sciences of “La Sapienza” University (Roma) and commissioned by Sogin [23]. This research integrates rheology of the lithosphere of the Italian peninsula with the active regional tectonics, by jointly analysing available geological, geo-structural and geophysical information. In [23] authors explored the whole Italian territory using a 25 × 25 km sized grid. With reference to the crustal thickness and depth of the lithospheric mantle, they calculated the local maximum differential stress for rupture of the lithosphere. Calculations were completed with (a) the analysis of the deformation vectors as measured by networks of GNSS permanent stations, (b) the stratigraphy of deep wells drilled by ENEL and AGIP; (c) the “database” of Italian major faults (DISS, ITHACA, GNDT). Results were synthesized in the “Maps of the maximum expected magnitude on geological-geophysical basis” for earthquakes potentially occurring within each of the 25 × 25 km cells.

Finally, the earthquakes spatial distribution was analysed based on the instrumental recordings from the ISIDE-INGV (<http://iside.rm.ingv.it>, accessed on 13 May 2021), which reports the active seismicity since 1985.

2.5. Holocene Uplift, Erosion and Sedimentation

A geomorphological analysis was achieved to test the hypothesis that a regional uplift, lasting since the Pleistocene-Holocene, is presently occurring in the area [32]. It relies on the interpretation of the numerous fluvial terraces and entrenched meanders that can be recognized along the course of the Dora Baltea river. Special attention was paid about fluvial terraces developing outside the moraine arc, which crosscuts the outwash plain south of Mazzè.

2.6. Hydrogeological Data

Hydrogeological constraints for RW repository localization are defined in the EC10 criterion and further technical specifications are given in the IC8 one. EC10 only takes into consideration piezometric levels of the superficial aquifer, moving all of the other technical issues to the IC8 criterion. EC10 is intended for testing the possibility that groundwater could interact with RW repository foundations compromising its degree of insulation, thus increasing the possibility of radionuclides transfer to the surrounding environment. If one compares EC10 with IC8, an unreasonable unbalance can be, immediately, detected. EC10 introduces the following exclusion conditions: (a) the proximity (300 m) of the area to superficial waterbodies (with an area > 1500 m²); (b) the presence of underground water field evidences (e.g., flooded crops, swamps, etc.); (c) the presence of springs or intake artefacts. These conditions do not take into account the actual groundwater level of the

aquifer (hereinafter called GL), nor the underground water flow, nor to the groundwater uses, nor the eventual presence of recharging areas of the deep aquifer (used for supplying drinking water). The latter, alone, represents a solid exclusion criterion. Instead, Sogin (according to ISPRA guidelines) delegated all of these concerns to IC8, whose weakness has already been discussed. Indeed, many open public and official data exist for easily deepening the analysis, making possible a more detailed description of the actual situation.

A further weakness of this approach is that the EC10 and IC8 criteria majorly focus on the near surface aquifer, being the one that can interact with the RW repository. No explicit concern is given about the “deep” aquifer providing drinking water to local communities. With the aim of demonstrating that the existing open data (PH, AF, W layers in Table 2) are sufficient to decode critical situations, ordinary GIS-based (SAGA GIS v.7.9 and QGIS 3.18.1) procedures were applied during the analysis.

Spatially continuous representations of the main local hydrogeological features were generated from the native PH and AF vector layers, by rasterization. This was obtained by spatial interpolation based on the “natural neighbour” algorithm as implemented in SAGA GIS [33]. A grid size of 100 m was selected during the rasterization. To achieve this task, native line vectors were converted (with densification, 1 point every 100 m) into point layers (see Figure 9). The correspondent variograms [34] were, therefore, generated to test the legitimacy of spatial interpolation, that was confirmed. Resulting raster layers (hereinafter called $PH(x,y)$ and $AF(x,y)$, respectively) were used for the following analyses. $PH(x,y)$ was preliminary validated, to ensure robustness of deductions in the following steps aimed at mapping the local groundwater level (GL). During this step, the 20% of points (randomly selected) were used as validation set. The local PH value at those positions (as coming from the regional data) was compared with the estimated one by spatial interpolation from $PH(x,y)$. MAE (Mean Absolute Error,) and RMSE (Root Mean Squared Error) [35] were used as accuracy parameters. To recover a proper representation of local groundwater level, $PH(x,y)$ was compared by grid differencing with the available DTM. A 100 m grid sized raster map of the superficial aquifer, hereinafter called $GL(x,y)$, was obtained and analysed with respect to the EC10 and IC8 criteria.

The Variance Propagation Law [36], involving DTM and $PH(x,y)$ accuracy (namely, σ_{DTM} and σ_{PH}), was applied (Equation (1)) to recover an appropriate estimate of the $GL(x,y)$ uncertainty (σ_{GL}). This was needed to properly consider groundwater table interference with the repository structure.

$$\sigma_{GL} = \sqrt{\sigma_{DTM}^2 + \sigma_{PH}^2} \quad (1)$$

Furtherly, seasonal variations of GL were taken into consideration while testing this condition. Estimates of GL variations in the area were found in literature (see Section 3).

2.7. Testing the EC12 Criterion

A rather complex exclusion criterion is the one related to the local settlements (EC12) that investigates spatial relationships between the repository and surrounding settlements. The approach proposed by Sogin [18,37,38] relies on the possibility of testing topological conditions, mainly related to the distance between the repository and neighbour-built areas, or technological-industrial facilities. Buffering, operated with reference to the flat distance between the site hosting the RW repository and the generic settlement structure, is the main spatial tool adopted within the procedure. Concerning both residential and productive areas, the reference geodatabase (polygon vector layer) used by Sogin was LOC2011 (see Table 2). In this layer, four types of settlements are considered: (a) towns/villages (“centri abitati”, code = 1); (b) group of houses (“nucleo abitato”, code = 2); (c) productive/industrial areas (“località produttive”, code = 3); (d) sparse houses (“case sparse” code = 4). Crucial importance has the meaning assigned to class 2, that in [18] is defined as “an inhabited locality, with no meeting place for people, consisting of a group of close houses hosting at least five families, with roads, paths, squares, farmyards, small gardens, small uncultivated grounds. The space inter houses is expected to be less than 30 m”.

In [18,37], three levels of analysis are proposed, each defining a buffering level: (a) “settlements” (1st buffering level) involving all polygons labelled as 1, 2 and 3 in LOC2011; (b) “local urbanisms” (2nd buffering level), involving only settlements having more than 20,000 inhabitants; (c) “metropolitan areas” (3rd buffering level), involving only the biggest Italian cities. This hierarchical approach aims at taking into consideration not only spatial relationships between settlements and the repository, but also those mutually existing among neighbour settlements and defining the local commercial/social tissue. In spite of this reasonable, and explicitly, defined procedure by Sogin for the application of the EC12 criterion, only the first level buffering was implemented to generate the CNAPI [18]. This corresponds to the application of a buffer zone around the polygons classified as 1, 2 or 3 in LOC2011. The size of the buffer was set to generate an area 10 times greater than the one presently occupied by the considered settlement. A minimum radius value of 1 km was, however, considered for smallest towns. The buffer was computed from the border of the mapped polygon, defining the settlement in the LOC2011 layer. In this framework, we explored the potential scenario that would have been found if the 2nd level buffering (“local urbanisms”) had been considered during the application of the EC12 criterion. The implemented procedure, managed by ordinary GIS tools, was the one reported in [37] with respect to the close municipality of Chivasso, being compliant with the requirements from Sogin (number of inhabitants > 20,000).

A further critical point in EC12 application by Sogin concerns the spatial granularity and updating of the LOC2011 layer used for the first level buffering. Two “groups of houses” (code = 2), namely “Cascina Giletta” and “Cascina Gabriella”, located close to the border of the TO-10 site, were not considered, since not mapped in the LOC2011 layer. Nevertheless, they were clearly mapped in the available BDTRE2021 layer and proved to be compliant with the requirements about: number of resident families (at least five, data supplied by the Mazzè local administration—Demographic Office); inter-houses distance (<30 m). Moreover, a bio-gas production site (that could be associated to the 3 code of the LOC2011 layer), located close to the NW part of the TO-10 site, was not considered. A new scenario was, therefore, generated including these additional polygons and the correspondent buffers (1 km radius).

3. Results and Discussions

Given the particular nature of this analysis where results are mainly discussions and interpretations of existing data, we decided to include results and discussions in a single section of the paper, making its reading easier and more effective. Consequently, the ordinary organization of the paper was changed, accordingly.

3.1. Geological, Tectonic and Seismogenic Analysis of the Area

The study area lays on Pleistocene fluvio-glacial sediments. It develops within a complex Miocene-to-Holocene geodynamic setting. During this period, the Apennine thrust fronts propagated north and northeast-ward below the Po plain, dislocating the active Alpine retrovergent units and the pre-Tertiary sedimentary series [22,39]. In particular, according to Festa et al. [40], the frontal Apennine thrusts deformed the Plio-Quaternary sediments along the Po plain fore deep basin (Figures 2 and 3). The CROP-ALPS 1 seismic reflection data made it possible to identify a major inverse fault (with a series of ramps and flats) that belongs to the Apennine domain and clearly dislocates and overthrusts the retrovergent south-Alpine units and the most superficial sedimentary sequence (Figure 3). This structure is outlined by a major discontinuity in the reflective traces, propagating from 8 km depth up to the surface. It can be observed that, besides the crystalline blocks, the fault affects the Mesozoic, the Tertiary, and the Plio-Quaternary units. The emplacement dynamics related to this fault generated a series of fault-propagation-folds and fault-bend folds [41] approaching the surface with a general northward vergence. Among these, the anticline that affects the clayey horizons outcropping in the Torrazza-Rondissone area, on the NW side of the Dora Baltea scarp.




Figure 2. A subset of the Structural Model of Italy by CNR [21]. The CROP ALP-1 seismic profile is shown in red. AFT, Apennine Frontal Thrusts; MFA, Median Front of Alpine retrovergent units; CL, Canavese Line; CA, Canavese Zone; SL, Sesia-Lanzo Zone; IZ, Ivrea Zone. Within the Po plain the tectonics of the area, north of AFT, is characterized by the major “Saluggia” syncline and by a system of syncline-anticline folds.

Concerning the interpretation of the above mentioned data, the tectonics of the area appear to be rather complex. This complexity was not detected by Sogin and no mention is given in [42]. Nevertheless, this issue has relevant implications with respect to tectonic uplift and seismic hazard of the Po plain region, where the TO-10 area is located. Here, both the active north-vergent tectonics of the Apennine margin (responsible for the Emilia 2012 earthquake), and the active south-vergent Alpine margin tectonics (involved in the genesis of the Verona 1117 earthquake, the Brescia 1222 earthquake and the Friuli 1976 earthquake) combine and interfere, within a relatively limited spatial volume, involving the upper crustal blocks. This configuration significantly increases the potential for stress accumulation, tectonic uplift, and consequent seismic hazards.

3.2. Seismic Hazard of the TO-10 Area

With focus on the above mentioned “Map of the maximum expected magnitude on geological-geophysical basis” for earthquakes potentially occurring within an area of 25 km × 25 km, some considerations can be done for the TO-10 site. Figure 4 shows the grid-units close to the Viverone Lake and the TO-10 area. This figure also reports the two main tectonic units underlying the Po plain and the numerical results of the study by La Sapienza University [23] for the quadrant that includes the TO-10 site. According to Figure 4, the expected magnitude in the area (6.5–6.7 Mw) is consistent with the one of the major earthquakes occurred within the Po plain in the past (Verona 1117 A.D., Brescia 1222 A.D.). The authors of the map suggest to adopt a “revised magnitude” (6.2–6.3 Mw) to refine those estimates and better fit their model.




Figure 3. Internal section of the ECORS-CROP project (also known as CROP ALP-1) along the alignment Castellamonte-Caluso-Lamporo. The TO-10 site location is shown in red. Original data from Roure et al. [26] have been revisited and reinterpreted also in the light of [43]. It can be noticed that the major fault ceases right below the Dora Baltea River scarp. The indication referring to “Cigliano” is the perspective reference from the point of view (located within the SW quadrant). The inset provides details of the structural setting (see text). PQ: Plio-Quaternary; M: Messinian; B: Burdigalian-Tortonian; Ol-Mi: Oligocene-Miocene (Gonfolite); PZ: South Alpine retrovergent units; LC: Lower Crust (granulites and related rocks of the Ivrea Zone); UM: Upper lithospheric Mantle. Major faults: thick black lines, dashed were approximate.




Figure 4. In yellow the considered 25 km × 25 km quadrants of the “Map of the maximum expected magnitude on geological-geophysical basis” (base from Google Earth). Numerical values are those reported in the Sogin DN-GS-00095 [23] for the quadrant containing the TO-10 site. Simplified traces of the Apennine Frontal Thrusts (AFT) and the Median Front of Alpine (MFA) retrovergent units are, also, reported.

With reference to the relationship of Sabetta and Pugliese [44], integrated with the coefficients of Bommer et al. [45] for variable focal mechanisms, the horizontal PGA max at the solid bedrock (category A) can be computed as a function of the epicentre distance. For a “precautionary” earthquake of 6.5 Mw (the minimum theoretical Magnitude, but slightly higher than the “Revised Magnitude”) with its epicentre within 5 km from the TO-10 site ($R_{\text{epi}} = 5$ km), the following accelerations can be found: $a_{\text{gmax}} = 0.46 \times g$ for a normal fault, $a_{\text{gmax}} = 0.48 \times g$ for a transcurrent fault and $0.59 \times g$ for a reverse fault. Doubling the radius ($R_{\text{epi}} = 10$ km), values become $0.30 \times g$, $0.32 \times g$, and $0.39 \times g$, respectively. Alternatively, while applying the relationship proposed by Ambraseys et al. [46] lower values (of about 25%) can be found. Therefore, even using the smaller, and optimistic, values from [46], maximum accelerations would be $>0.25 \times g$ for all types of faults if an earthquake occurred within a distance of 5 km from the TO-10 site. It is worth to remind that this value corresponds to the threshold defined in the EC2 criterion. Similarly, an earthquake occurring within a distance of 10 km from the TO-10 site would generate a maximum acceleration of $0.29 \times g$ for a reverse fault (the most likely to occur in the TO-10 area, given the active compressional tectonics) which is still higher than the $0.25 \times g$ threshold value.

We remark that these results underestimate the actual local seismic acceleration, because the gravel-sands sediments outcropping in the area may amplify the above PGA values.

Additionally, the high seismic risk of the area is underscored by the earthquake’s distribution mapped in the ISIDE-INGV Catalogue. The positions of the recorded epicentres within a distance of 70 km from Mazzè show that within a distance of about 25 km from the municipality of Santhià (the area includes the present nuclear sites of Saluggia and Trino Vercellese) no earthquake was recorded with magnitudes $M_L \geq 1.0$ (Figure 5).




Figure 5. Schematic representation of epicentral positions of seismic events, with $M_L \geq 1$, observed within a 70 km radius around Mazzè according to the ISIDE-INGV Catalog. The traces of the Apennine Frontal Thrusts (AFT, according to DISS database) and the Median Front of Alpine (MFA) retrovergent units are also reported.

This situation, interpreted by considering the active compressional tectonics existing in the area [47,48] and the high density of earthquakes epicentres that occur all around, defines a “seismic gap”. As postulated by McCann et al. [49], these sectors of the lithosphere show a “high seismic risk” since the seismic energy is not regularly dissipated as occurring in the neighbouring areas. Therefore, the accumulation of elastic strain can ultimately favour the rupture of significant portions of the crust, triggering higher magnitude earthquakes [50,51].

Figure 5 also shows the innermost position of the underlying alpine units and the western segment of the Apennine frontal thrusts, as reported in the DISS “database”

(<http://diss.rm.ingv.it/diss/> accessed on 13 May 2021). These Apennine trusts show a disjunction close to the city of Chivasso, where a NNO-SSE tear-fault apparently follows the distribution of hypocentres at the western edge of the cited seismic gap. Sue et al. [52] suggest a left-lateral component for this fault that could be linked to a counter-clockwise rotation of the Adria microplate, undergoing compression against the Alpine orogen. In conclusion, although the EC2 criterion of the Technical Guide n. 29 of ISPRA is limited and inaccurate (since the time window for evaluating seismicity is restricted to the actually historically recorded earthquakes, and does not take into account the “effective time-scale” of geological processes), the above data strongly indicate that the TO-10 area can be considered at “high seismic risk” and, therefore, not adequately safe for hosting the National Nuclear Waste Repository.

3.3. Holocene Uplift, Erosion and Sedimentation

The area, extending Southward of the Ivrea moraine arc, consists of glacio-fluvial sediments deposited in the frontal zones of the Pleistocene glaciers that descended along the Aosta Valley from the Monte Bianco Group [53–55]. Area slopes range from 1.6° , close to the frontal moraines in the north, to 0.6° in its southern part, where the Monferrato hills (the front of the Apennine) interrupt the plane and the Po River flows eastward. The fluvio-glacial plane is dissected NW-SE by a deep incision that forms the “cañon” of the Dora Baltea river (Figure 6—left). This cañon has been, and is currently being, cut in the unconsolidated glacio-fluvial deposits for a depth of about 60 m and a width of 2200 m. The sides of the cañon are occupied by a set of fluvial terraces and abandoned riverbeds, that are mapped in Figure 6, [54]. A set of older glacio-fluvial terraces can be also identified in the glacio-fluvial plane bordering the cañon including the “Valle della Motta” (close to the TO-10 area) drainage system. The Dora Baltea cañon exits the Ivrea moraine arc, forming four major entrenched meanders, signed on their top by paleo-meanders, fluvial drainages and terraces; these testify that the river in the past was at a higher altitude than presently, although flowing close to its equilibrium profile. On the flanks of the canon, 7 terraces can be recognized ranging from the younger ones, lying along the river, to the older ones found at higher altitudes. Downhill of this first section, the river anatomizes (with no more entrenched meanders) and flows into several riverbeds with few terraces left on the sides. Loose, easy-erodible, glacio-fluvial sediments that constitute both the sides of the Dora Baltea cañon up to the very top and the high-erosion potential of this river indicate a very young age for the formation of the cañon (younger than the latest Pleistocene glaciation). It is worth to remind that the Dora Baltea is the largest tributary of the NW sector of the Po River basin; in 2000 the Dora Baltea flooded with a flowrate of about $3000 \text{ m}^3/\text{s}$ at the intersection with the Po River, itself having a flowrate of about $5000 \text{ m}^3/\text{s}$ [56].

The fast erosion of the cañon is confirmed by the absence of secondary tributary streams of the Dora Baltea on its flanks, where numerous perched springs can be found. Authors’ interpretation leads to admit that the erosion of the cañon took place after the end of the latest glacial episode about 25,000 years ago [54], during a continued uplift of the area. This is, also, confirmed by the numerous terraces and abandoned riverbeds of the paleo-Dora Baltea parallel to the Po River east of their junction [48]. In summary, this complex geomorphological situation, which involves fluvio-glacial terraces, fluvial terraces and entrenched meanders, strongly supports the idea that the area is undergoing an uplift. This is estimated in more than $1.5 \text{ mm}/\text{y}$ [57]. If one would assume a reasonable uplift of about $2 \text{ mm}/\text{y}$, during the last 30,000 years (i.e., since the latest glacial maximum) the total expected uplift would be in the order of 60 m; this value appears to be consistent with the height difference between the present FG-3 level and the Dora Baltea River.




Figure 6. (a) Map of local terraces. Recent terraces within the Dora Baltea River cañon are indicated with DB-1 (youngest) to DB-7 (oldest). DB-0 is the active riverbed. Older fluvio-glacial plane terraces are indicated with FG-1 (youngest) to FG-6 (oldest). FG-0 is the Po River sediments layer. The “Valle della Motta” terraces are labelled with VM-1 to VM-4, while the VM-0 is the active drainage. Note that there are no secondary streams developing along the side of the Dora Baltea River cañon. The “Valle della Motta” is the long drainage that begins in the Ivrea moraines (as abandoned glacial outwash river) in the North and extends all the way to the bottom of the figure. (b) Shaded relief from the regional 5×5 m grid sized DTM of the TO-10 area. A set of terraces can be recognized in the glacio-fluvial sediments. The Dora Baltea cañon cuts these sediments in a NW-SE direction on the right side of the image.

A recent uplift is also proposed by Giraudi [47] for the terraces along the Paleo-Dora Baltea and the Po river, at the East of the present confluence between Dora Baltea and Po river. An additional uplift was observed at the west of this area, being responsible of the modification of the course of the Po river [58]. Consequently, it would appear anomalous if no uplift affected the area comprised between these two sectors, given the identical tectonic settings with the Apennine Frontal Thrusts (AFT) overthrusting the retrovergent units of the Alpine range (which are currently uplifting at a rate of 1.2 mm/y [59]).

Additionally, looking at Figure 6, it can be noticed that the TO-10 area is crosscut by the “Valle della Motta” drainage system, where surface and near-surface materials (gravel, sands and discontinuous thin silty-clayey horizons) have been re-worked and redeposited during the Holocene. The Regione Piemonte in [25] classified the southern sector of this drainage as at high risk for periodic flooding (return times varying between 25 and 50 years). Moreover, the nature and the geometry of the sedimentary cover series, as well as their high hydraulic conductivity (10^{-2} – 10^{-3} m/s) [24], categorically exclude the presence of a “geological barrier” to the escape of radionuclides, that IAEA standards require. All of these considerations make it possible to confirm that the area matches EC4 and EC5 criteria, resulting in not being suitable to host the RW repository also from this point of view.

3.4. Hydrogeological Data

In order to test the EC10 criterion, a preliminary analysis of macro-evidences from open hydrogeological data was achieved. In Figure 7, the native layers from the regional geoportale are shown for the whole Piemonte Region to make evident that the TO-10 site is located in one of the most strategic and critical areas for groundwater dynamics. PH and AF layers refer to the superficial aquifer; differently, the RS layer maps the recharging area of the deep aquifer, that provides drinkable water to a great part of the Piemonte region.

In Figure 8, the area hosting the TO-10 site is specifically investigated with respect to the above-mentioned layers, showing that: (a) the site partially lays in the recharging area of the deep aquifer (NE part); (b) a system of wells is present in the area. In particular, eight wells for water catchment from the deeper aquifer (some of them for drinking water supplying) fall in, or nearby the area, making local population and agricultural activities highly exposed to the environmental risk associated with the RW repository.




Figure 7. Maps showing the available AF (left) and PH (right) layers as obtained from the Piemonte Region geoportal. Reference system is WGS84 UTM 32N.




Figure 8. (left) Hydrogeological sketch of the TO-10 site and its surroundings. Contour lines for isopiezometric heads show the groundwater table geometry. Light blue areas report the recharge areas of the deep aquifer (that provides drinking water). In yellow the main towns around the area; blue lines represent the main hydrological network. (right) Detail of the TO-10 area and its surroundings: (a) the recharge area of the deep aquifer is partially included in the site; (b) several wells are located nearby or within the area; eight out of them catch the water from the deep aquifer. Reference system is WGS84 UTM 32N.

The whole scenario becomes critical if we consider the possibility of leakage from the repository basement coupled with the location of wells within the site and south of it proceeding downhill and of the nearby Dora Baltea cañon. A possible contamination front of radioactive aqueous solutions, in fact, could not only compromise the local deep aquifer, but also reach the Po river, exponentially increasing the nuclear risk within the whole Po basin.

To give a continuous representation of the main hydrogeological features in the area, native vector layers (namely PH and AF) were rasterized. To verify the suitability of spatial interpolation, correspondent points layers (Figure 9a), were used to test spatial autocorrelation by variogram (Figure 9b, for PH only). Variograms proved that spatial autocorrelation exists up to about 20 km, making possible to interpolate.




Figure 9. (a) Contour lines mapping PH and the correspondent points used during interpolation. (b) Variogram from PH values testifying that a spatial autocorrelation exists (range is about 20 km). Similar results were found for AF.

Interpolation was operated by means of the “natural neighbour” technique generating two raster maps, $PH(x,y)$ and $AF(x,y)$, with a grid size of 100 m (corresponding to about one tenth of the average planar distance between the mapped contour lines). With special concern about the main issue considered in the EC10/IC8 criteria, i.e., the possibility that an interference can occur between the superficial aquifer and the repository structure, $S(x,y)$ was generated, mapping the distance of the groundwater table from the ground surface. $S(x,y)$ was generated by comparing $PH(x,y)$ with the available DTM by grid differencing.

Validation of $PH(x,y)$ was operated with respect to the 20% (4532) of the points obtained while converting the correspondent line vector (a total of 22,660 points). MAE and RMSE values were found to be 0.44 m and 0.79 m, respectively. According to [35], MAE is a more robust estimator of actual accuracy of model. Consequently, we assumed it as the reference one to get an estimate of the theoretical accuracy of $S(x,y)$.

The latter can be estimated relating uncertainty of DTM ($\sigma_{DTM} = \pm 0.33$ m) and $PH(x,y)$ ($\sigma_{PH} = \pm 0.44$ m) by the Variance Propagation Law of Equation (1). Accordingly, it was found that the theoretical accuracy of $S(x,y)$ was ± 0.55 m.

$PH(x,y)$, $AF(x,y)$ and $S(x,y)$ raster maps are reported in Figure 10. They show the area at two different scales: the landscape one (Figure 10a–c) aimed at locating the TO-10 site into the general hydrogeological system; the local one (Figure 10d–f) focusing on the local conditions of the TO-10 site and reporting some numerical values useful to recover the proper quantitative reference.




Figure 10. Raster maps of: (a) $PH(x,y)$: altitude a.s.l. of the piezometric head of the aquifer (landscape level); (b) $AF(x,y)$: altitude a.s.l. of the floor of the aquifer (landscape level); (c) $GL(x,y)$: groundwater level (meters from the ground) of the aquifer (landscape level); (d) $PH(x,y)$ in the TO-10 site; (e) $AF(x,y)$ in the TO-10 site; (f) $GL(x,y)$ in the TO-10 site. In (a–c) blue polygon defines the TO-10 area. In (d–f) some numerical values are reported for random pixels. Raster maps were generated by spatial interpolation from line vector layers with a grid size of 100 m. Reference system is WGS84 UTM 32N.

A further specification is given in Figure 11 where it can be observed that the distance of the groundwater table from the ground ranges between about 11 m (NW part), down to 4.8 m (central/eastern part, yellow squared). If we account for the most cautious conditions, these values have to be refined taking into consideration seasonal variations of PH and uncertainty of $S(x,y)$. The former can be deduced from [24] that, for a site located close to the TO-10 site, eastward in the Vercelli plain, reports an average yearly seasonal variation of the local groundwater table of about ± 4 m. The joint effect of measure uncertainty and seasonal variation increases to ± 4.55 m the cautionary value that one has to consider when mapping the local groundwater. This value makes possible that the actual level of the superficial aquifer in the area could even reach the ground surface and significantly affect the RW repository basement and its foundations.




Figure 11. An alternative visualization of the groundwater level (m from the ground) in the TO-10 site. A simplified colour strategy permits to immediately locate zones where groundwater average level is lower than 6 m (red lines), between 6 and 8 m (blue lines) and over 8 m (green lines). Particular meaning has the yellow squared area, introducing a technical limitation/exclusion issue exactly where the EC12 criterion is weaker (compare next section). Reference system is WGS84 UTM 32N.

It is worth stating that the repository lower level, where the higher activity scoriae are supposed to be stored, is expected to be located up to about 10 m depth ([60] p. 47).

This hydrogeological vulnerability of the area was well known to Sogin since 2005: in a paper published in cooperation with the Politecnico of Torino [20], the TO-10 site area was indicated as a *high vulnerability* one; it is therefore surprising that this site could have entered (and gained the top of) the list of the potential suitable sites to host the RW repository.

This scenario can get worse if we consider the concentrated channel network cross-cutting the area and supplying water to the local crops. In the light of the above, it can be easily demonstrated that the data reported by Sogin have not been analysed and rigorously interpreted to assess the vulnerability of the TO-10 site. Sogin itself, in DNG S00102 [18] and DNG S00304 [61], indicates that further in-depth studies are needed (by applying the IC8 criterion), thus diverting the problem from the exclusion criterion EC10 to the investigation one IC8. Indeed, the area TO-10 had to be excluded in the first place by Sogin.

3.5. Testing the EC12 Criterion

The first issue about the application of this criterion is the general ambiguity of the procedure outlined by Sogin. Advanced and well-designed strategies of investigation, mainly hierarchical and addressed to evaluate local relationships among neighbouring inhabited centres, are described in [37] and somehow revisited in [18,62] (see [18] at page 158). Nevertheless, only some of the above indications have been applied by Sogin while redacting the CNAPI map. In particular only the first level of investigation was achieved, that relies on the direct application of a buffer (as previously described) to the LOC2011 polygons having codes 1, 2, 3. Topological relationships related to “local urbanisms” and “metropolitan areas” were not considered at the current stage, although reported in the above mentioned documents. In this work we implemented the analysis related to the “local urbanisms” as described in [37]; accordingly, the Chivasso municipality (having more than 20,000 inhabitants), located close to the TO-10 site, was considered and the LOC2011 layer used as geometrical basis. We found that the “local urbanism” of Chivasso (relating

all the settlements included within a distance of 5 km from the borders of its main centre) impacts definitely the TO-10 area (Figure 12a). The suitable area of the TO-10 site, that presently sizes about 515 ha, would be reduced to about 44 ha, making it absolutely inadequate for hosting the national repository, whose size is expected to be around 100–110 ha (see [13]).




Figure 12. (a) 2nd level buffer (“local urbanism”) of the Chivasso municipality. The external blue polygon is the buffer area around the convex-hull defining the local urbanism of Chivasso mapped according to the procedure reported in [37]. (b) 1st level buffers (circular, 1 km radius) around the three settlements (Cascina Giletta, Cascina Gabriella and the Villosio bio-gas production plant) that Sogin didn’t consider during its evaluation, since not mapped in the ISTAT LOC2011 layer. In (b) power and gas lines layouts are also reported together with correspondent safety buffers (200 m for power lines and 100 m for gas lines) as required by Italian regulations.

Additionally, even neglecting the Chivasso “local urbanism” analysis, strong constraints would come if the three earlier mentioned settlements of “Cascina Giletta”, “Cascina Gabriella” and the Villosio bio-gas plant (Figure 12b) were considered during the 1st level buffering.

In fact, the correspondent 1 km buffers split the TO-10 site into two separated areas, the greatest reaching about 124 ha. Given the resulting shape of the residual suitable area the preliminary project of the repository proposed by Sogin [13] is practically unfeasible. Moreover, this remaining area is located exactly where the groundwater table is confined at a lower depth (less than 5 ± 4.55 m from the ground, see Figure 11).

The TO-10 site is also crosscut by remarkable technological facilities, namely two power lines and a pipeline, whose layouts are reported in (Figure 12b) together with their proper safety buffers (200 m for power lines and 100 m for pipelines) as required by Italian regulations. Additional concerns may include the possible domino effects related to accident risk involving the coexistence, within a limited space, of the repository, of the cited technological lines and the nearby Villosio bio-gas plant (possibly recalling the CE15 criterion—“areas characterized by the presence of industrial activities showing a risk of relevant accident, dams and artificial hydraulic barriers, airports or operational military areas” [18]).

4. Conclusions

The systematic analysis of available geological and geophysical data clearly demonstrates that the area TO-10 is located within a tectonically active geodynamic environment. Moreover, the analysis of recent instrumental seismic data, collected since the early eighties (ISIDE-INGV Catalogue) indicates the existence of a “seismic gap” in this sector of the Po plain that, coupled with the occurrence of regional uplift [57–59], supports the idea that this sector of the Po plain could be the “locus” of major future earthquakes. For these reasons the area TO-10 clearly appears, already at this step of the procedure, matching the EC2 and EC3 criteria, definitely resulting not suitable for hosting a safe, long-lasting nuclear repository. Additionally, with special concerns about the analysis of the “Motta Valley” sector, was possible to verify that the TO-10 site also matches the CE4 and CE5 criteria.

As far as the local hydrogeological situation is concerned (EC10 and IC8 criteria), with reference to the available open data from the Piemonte Region geoportal, it was possible to demonstrate that the TO-10 site is located in a critical area. In particular: (a) the recharging area of the deep aquifer providing drinking water to great part of the South Piemonte, partially develops in the TO-10 site; (b) after mapping GL by spatial interpolation from native data, it was found that the depth of the ground water table can significantly interfere with the basement of the repository. All of these facts make possible to definitely state the not suitability of the TO-10 site also from the hydrogeological point of view.

The application, by GIS tools, of the EC12-related procedure, mapping the “local urbanisms”, made possible to highlight that the TO-10 site, greatly develops within the local urbanism buffer of the close municipality of Chivasso. Moreover, it was found that three important settlements (mapped on official maps from the Piemonte Region) were not considered by Sogin; related buffers would erode a great part of the TO-10 site making it drastically smaller. These findings from the CE12 criterion permit to conclude that the TO-10 site is located in a highly populated area and potentially can compromise important social and economic activities in this part of Italy. This situation makes the area compliant with the EC12 criterion and therefore not suitable to be included in the list of potential suitable sites by Sogin.

Additionally, one has to consider that the eventual “commissioning” of the TO-10 site, together with the “decommissioning” of the near Saluggia and Trino sites, currently hosting the most of the Italian nuclear wastes, would involve an accumulation of health and environmental risks for local population, thus making this part of Italy an hot-spot from the nuclear risk point of view. It is also curious that, in case of the TO-10 site selection, nuclear wastes would be transferred from areas showing an “extremely high hydrogeological vulnerability” (Saluggia and Trino) to a new one (TO-10) showing a “high hydrogeological vulnerability” [20].

Concluding, in this work we tried to synthetically outline the “issues and perplexities” related to the procedure that many Italian territories (67 municipalities) are currently handling for safely preserve the health of their inhabitants and the conservation of their surrounding environment. It is our hope that this document could somehow stimulate a new deal in the Sogin (and future national planning) selection procedure where official open data will play a major and fundamental role, making it possible to speed up the times of the selection itself and saving public money.

Author Contributions: Author contributions are consistent with authors’ specific field of knowledge. E.B.-M. was responsible of the entire work conceptualization and organization and referent for the EC10/IC8 and EC12 related analysis. A.B. and C.C. were referents for CE2/IC2 and EC3/IC3 related analysis. All of the authors, each for its part, participated in methodology, software, formal analysis, investigation, resources, data curation, writing—original draft preparation, visualization, supervision. To be completed if the paper will be accepted. All authors have read and agreed to the published version of the manuscript.

Funding: All the three authors significantly contributed to this paper. E.B.-M. and C.C., contributed to this research because both are residents of the Mazzè (TO) municipality and the topic is directly related to their field of interest. A.B. was under a contract by the Mazzè (TO) Municipality for determining the geological and hydrogeological settings of the TO-10 area.

Institutional Review Board Statement: Not applicable.

Data Availability Statement: The work almost entirely relies on public and open data from institutional archives or, directly, from the Sogin CNAPI website. The list of the archives is given below: *Geographical Data/Maps* (a) <https://www.geoportale.piemonte.it/cms/>, accessed on 13 May 2021, (b) <https://www.istat.it/it/archivio/104317/>, accessed on 13 May 2021. *Sogin CNAPI documents* (a) <https://www.repositorynazionale.it/documenti/pagine/documenti-progetto-preliminare.aspx/>, accessed on 13 May 2021.

Conflicts of Interest: The authors declare the above-mentioned relationships with the TO-10 territory and Mazzè (TO) municipality administration. Their work was specifically aimed at testing reliability and reasonability of the results from the Sogin procedure with the aim of ensuring safety for local population. The analysis and interpretation of data rely on scientific basis and interpreted data comes from official archives. The authors also remark that considerations about procedure weaknesses are strictly personal even if based on widely accepted criteria from the scientific engineering community.

References

1. South, N. (Eds.) *Issues in Green Criminology*; Beirne, P.; Willan: London, UK, 2007; ISBN 978-1-84392-634-4.
2. Giusti, L. A Review of Waste Management Practices and Their Impact on Human Health. *Waste Manag.* **2009**, *29*, 2227–2239. [[CrossRef](#)] [[PubMed](#)]
3. Rechard, R.P. Historical Relationship between Performance Assessment for Radioactive Waste Disposal and Other Types of Risk Assessment. *Risk Anal.* **1999**, *19*, 763–807. [[CrossRef](#)] [[PubMed](#)]
4. Murray, R.L. *Understanding Radioactive Waste*; Battelle: Columbus, OH, USA, 1994.
5. Lutze, W. *Radioactive Waste Forms for the Future*; North Holland: Amsterdam, The Netherlands, 1988; ISBN 978-0-444-87104-6.
6. Brookins, D.G. *Geochemical Aspects of Radioactive Waste Disposal*; Springer Science & Business Media: Berlin, Germany, 2012.
7. El-Ghonemy, H.; Watts, L.; Fowler, L. Treatment of Uncertainty and Developing Conceptual Models for Environmental Risk Assessments and Radioactive Waste Disposal Safety Cases. *Environ. Int.* **2005**, *31*, 89–97. [[CrossRef](#)]
8. *International Atomic Energy Near Surface Disposal Facilities for Radioactive Waste*; IAEA SAFETY STANDARDS SERIES; IAEA: Vienna, Austria, 2014.
9. Won, K.; Han, J.; Bonne, A. Radioactive Waste Disposal: Global Experience and Challenges. *IAEA Bull.* **1997**, *39*, 33–41.
10. *Radioactive Waste Management*, 2nd ed.; Saling, J.H.; Fentiman, A.W. (Eds.) Routledge: Boca Raton, FL, USA, 2017; ISBN 978-0-203-74134-4.
11. Tsoulfanidis, N.; Cochran, R.G. Radioactive Waste Management. *Nucl. Technol.* **1991**, *93*, 263–304. [[CrossRef](#)]
12. ISPRA. Guida Tecnica n. 29—Criteri per La Localizzazione Di Un Impianto Di Smaltimento Superficiale Di Rifiuti Radioattivi a Bassa e Media Attività. ISPRA: Roma, Italy, 2014.
13. Sogin spa. DN GE 00050—Progetto Preliminare—Possibili Adattamenti Della Planimetria Generale DN; Sogin spa: Roma, Italy, 2015.
14. Skidmore, A.K.; Bijker, W.; Schmidt, K.; Kumar, L. Use of Remote Sensing and GIS for Sustainable Land Management. *ITC J.* **1997**, *3*, 302–315.
15. Joerin, F.; Musy, A. Land Management with GIS and Multicriteria Analysis. *Int. Trans. Oper. Res.* **2000**, *7*, 67–78. [[CrossRef](#)]
16. Borgogno-Mondino, E.; Fabietti, G.; Ajmone-Marsan, F. Soil Quality and Landscape Metrics as Driving Factors in a Multi-Criteria GIS Procedure for Peri-Urban Land Use Planning. *Urban For. Urban Green.* **2015**, *14*, 743–750. [[CrossRef](#)]
17. Sogin spa. DN GS 00226—Proposta Di Ordine Di Idoneità Delle Aree CNAPI e Relativa Procedura a Seguito Del Nulla Osta Del 30/12/2020. Sogin spa: Roma, Italy, 2020.
18. Sogin spa. DN GS 00102—Basi Teoriche e Modalità Di Applicazione Dei Criteri per La Realizzazione Della CNAPI; Sogin spa: Roma, Italy, 2020.
19. ISPRA. Guida Tecnica n. 30- Criteri Di Sicurezza e Radioprotezione per Depositi Di Stoccaggio Temporaneo Di Rifiuti Radioattivi e Di Combustibile Irraggiato; ISPRA: Roma, Italy, 2020.
20. Civita, M.; De Maio, M.; Chiaravalli, F.; Buonone, E. Studio Della Vulnerabilità Dell'acquifero Libero Superficiale Nell'ambito Della Caratterizzazione Ambientale Di Un Sito Nucleare; GEAM Torino: Colorno, Italy, 2005; pp. 1–10.
21. Società Geologica Italiana Modello Strutturale d'Italia. Available online: <https://www.socgeol.it/438/structural-model-of-italy-scale-1-500-000.html> (accessed on 7 May 2021).
22. Università dell'Insubria, D di S. ed A.T.; Sogin spa. DN GS 00223—Studio Del Quadro Conoscitivo Relativo Alla Pericolosità Di Fagliazione Superficiale Su Aree Selezionate—RELAZIONE FASE 2; Sogin spa: Roma, Italy, 2015.
23. Università Sapienza di Roma. DN GS 00095—Valutazione Della Sismicità Del Territorio Italiano—Relazione Finale—Studio. Università Sapienza Di Roma; Sogin spa: Roma, Italy, 2014.
24. De Luca, D.A.; Lasagna, M.; Debernardi, L. Hydrogeology of the Western Po Plain (Piedmont, NW Italy). *J. Maps* **2020**, *16*, 265–273. [[CrossRef](#)]
25. Regione Piemonte. *Direttiva Alluvioni- Mappa Di Pericolosità e Rischio Alluvioni, Scenari Di Pericolosità*; Regione Piemonte: Torino, Italy, 2019.
26. Roure, F.; Polino, R.; Nicolich, R. Early Neogene Deformation beneath the Po Plain: Constraints on the Post-Collisional Alpine Evolution. *Mémoires Société Géologique Fr.* **1990**, *156*, 309–321.
27. Bernabini, M.; Nicolich, R.; Polino, R. Seismic Lines CROP-ECORS across the Western Alps—Le Linee Sismiche CROP-ECORS Attraverso Le Alpi Occidentali. *Mem. Descr. Carta Geol. D'It. LXII* **2003**, 89–96.
28. Ministero Delle Infrastrutture. *DECRETO 14 Gennaio 2008 Approvazione Delle Nuove Norme Tecniche per Le Costruzioni.*; Gazzetta Ufficiale: Roma, Italy, 2008.
29. INGV Seismic Hazard Map. Available online: <http://esse1.mi.ingv.it/> (accessed on 13 May 2021).
30. INGV Parametric Catalogues of Italian Earthquakes. Available online: <http://emidius.mi.ingv.it/CPTI/> (accessed on 13 May 2021).
31. INGV Catalogue of Strong Earthquakes in Italy. Available online: <http://storing.ingv.it/cfti/cfti5/> (accessed on 13 May 2021).

32. Mangelsdorf, J.; Scheurmann, K.; Weiß, F.-H. Investigations in River Morphology. In *River Morphology*; Springer: Berlin, Germany, 1990; pp. 193–210.
33. Quanfu Fan, A.E.; Koltun, V.; Krishnan, S.; Venkatasubramanian, S. Hardware-Assisted Natural Neighbor Interpolation. In Proceedings of the the Seventh Workshop on Algorithm Engineering and Experiments and the Second Workshop on Analytic Algorithms and Combinatorics, Vancouver, BC, Canada, 22 January 2005.
34. Borgogno Mondino, E.C.; Fissore, V.; Lessio, A.; Motta, R. Are the New Gridded DSM/DTMs of the Piemonte Region (Italy) Proper for Forestry? A Fast and Simple Approach for a Posteriori Metric Assessment. *iForest Biogeosciences For.* **2016**, *9*, 901–909. [[CrossRef](#)]
35. Chai, T.; Draxler, R.R. Root Mean Square Error (RMSE) or Mean Absolute Error (MAE)?—Arguments against Avoiding RMSE in the Literature. *Geosci. Model Dev.* **2014**, *7*, 1247–1250. [[CrossRef](#)]
36. Jeudy, L.M. Generalized Variance-Covariance Propagation Law Formulae and Application to Explicit Least-Squares Adjustments. *Bull. Géodésique* **1988**, *62*, 113–124. [[CrossRef](#)]
37. Karrer, S.F. DN GS 00198—*Dimensionamento Fisico Del Criterio Di Localizzazione CE12 Analisi Preliminare—Report 02*; Sogin spa: Roma, Italy, 2015.
38. Karrer, S.F. DN GS 00227—*Dimensionamento Fisico Del Criterio CE12—Grado Di Urbanizzazione Scala Nazionale. Proposta Metodologica (REV.01)*; Sogin spa: Roma, Italy, 2015.
39. Mosca, P. Neogene Basin Evolution in the Western Po Plain (NW Italy): Insights from Seismic Interpretation, Subsidence Analysis and Low Temperature (U-Th)/He Thermochronology. Ph.D. Thesis, Vrije Universiteit Amsterdam, Netherlands Research School Geology (NSG), Amsterdam, The Netherlands, 2006.
40. Festa, A.; Dela Pierre, F.; Piana, F.; Fioraso, G.; Lucchesi, S.; Boano, P.; Tamberlani, F. *Note Illustrative Della Carta Geologica d'Italia Alla Scala 1:50,000. Foglio 156 'Torino Est'*; ISPRA, Istituto Superiore per la Protezione e la Ricerca Ambientale: Roma, Italy, 2009.
41. Suppe, J. *Principles of Structural Geology*; Prentice-Hall: Englewood Cliffs, NJ, USA, 1985; ISBN 978-0-13-710500-7.
42. Sogin spa. DN GS 00147—*Inquadramento Geologico, Naturalistico e Antropico Dell'area TO-10*; Sogin spa: Roma, Italy, 2020.
43. Marchant, R.H.; Stampfl, G.M. *Crustal Lithospheric Structure of Western Alps: Geodynamic Significance*; Pfiffner, O.A., Lehner, P., Heitzmann, P., Mueller, S., Steck, A., Eds.; Birkhäuser Verlag: Basel, Switzerland, 1997; Vol. Deep Structure of the Swiss Alps: Results of NRP 20.
44. Sabetta, F.; Pugliese, A. Estimation of Response Spectra and Simulation of Nonstationary Earthquake Ground Motions. *Bull. Seismol. Soc. Am.* **1996**, *86*, 337–352.
45. Bommer, J.J.; Douglas, J.; Strasser, F.O. Style-of-Faulting in Ground-Motion Prediction Equations. *Bull. Earthq. Eng.* **2003**, *1*, 171–203. [[CrossRef](#)]
46. Ambraseys, N.N.; Douglas, J.; Sarma, S.K.; Smit, P.M. Equations for the Estimation of Strong Ground Motions from Shallow Crustal Earthquakes Using Data from Europe and the Middle East: Horizontal Peak Ground Acceleration and Spectral Acceleration. *Bull. Earthq. Eng.* **2005**, *3*, 1–53. [[CrossRef](#)]
47. Giraudi, C. The Evolution of the Northernmost Apennine Front (Piedmont, Italy): Plio-Pleistocene Sedimentation and Deformation in the Po Basin and Monferrato Hills. *Alp. Mediterr. Quat.* **2016**, *29*, 45–65.
48. Giraudi, C. The Climate-Triggered Western Shift of the Confluence between the Dora Baltea and Po Rivers (North-Western Italy) during the Late Holocene. *Holocene* **2019**, *29*, 432–444. [[CrossRef](#)]
49. McCann, W.R.; Nishenko, S.P.; Sykes, L.R.; Krause, J. Seismic Gaps and Plate Tectonics: Seismic Potential for Major Boundaries. In *Earthquake Prediction and Seismicity Patterns*; Wyss, M., Ed.; Contributions to Current Research in Geophysics; Birkhäuser: Basel, Switzerland, 1979; pp. 1082–1147, ISBN 978-3-0348-6430-5.
50. Nishenko, S.P. *Earthquake Hazards and Prediction, Encyclopedia of Solid Earth and Geophysics, Edited by James, DE*; Van Nostrand Reinhold: New York, USA, 1989.
51. Wyss, M.; Wiemer, S. How can one test the seismic gap hypothesis? The case of repeated ruptures in the Aleutians. In *Seismicity Patterns, Their Statistical Significance and Physical Meaning*; Springer: Basel, Switzerland, 1999; pp. 259–278.
52. Sue, C.; Delacou, B.; Champagnac, I.; Cecile, A.; Tricart, P.; Burkhard, M. Extensional Neotectonics around the Bend of the Western/Central Alps: An Overview. *Int. J. Earth Sci.* **2007**, *96*, 1101–1129. [[CrossRef](#)]
53. Gianotti, F. Stratigrafia Dell'Anfiteatro Morenico Di Ivrea. Unpublished Ph. D. Thesis, Universitadi Torino, Torino, Italy, 2007; 178p.
54. Gianotti, F.; Forno, M.G.; Ochs, S.I.; Giovanni, M.; Cesare, R. Stratigraphy of the Ivrea Morainic Amphitheatre (NW Italy). An Updated Synthesis. *Alp. Mediterr. Quat.* **2015**, *28*, 29–58.
55. Gianotti, F.; Forno, M.G.; Ivy-Ochs, S.; Kubik, P.W. New Chronological and Stratigraphical Data on the Ivrea Amphitheatre (Piedmont, NW Italy). *Quat. Int.* **2008**, *190*, 123–135. [[CrossRef](#)]
56. ARPA Pieonte. *EVENTI ALLUVIONALI IN PIEMONTE 13—16 OTTOBRE 2000—Analisi Meteorologica e Idrologica, 1.4 Analisi Idrometrica*; I.G.E.R. srl—Viale C. T. Odiscalchi: Roma, Italy, 2003; ISBN 88-448-0051-9.
57. Arca, S.; Beretta, G.P. Prima Sintesi Geodetico-Geologica Sui Movimenti Verticali Del Suolo Nell'Italia Settentrionale (1897–1957). *Boll. Di Geod. E Sci. Affin.* **1985**, *44*, 125–156.
58. Forno, M.G.; Gianotti, F. The Turin Fluvial Terraces as Evidence of the New Holocene Setting of the Po River. *J. Maps* **2020**, 1–11. [[CrossRef](#)]

59. Kahle, H.-G.; Marti, U.; Geiger, A.; Wirth, B.; Gubler, E.; Rothacher, M.; Gurtner, W.; Beutler, G.; Bauersima, I. Recent Crustal Movements, Geoid and Density Determination: Contribution from Integrated Satellite and Terrestrial Measurements. In *Deep Structure of the Swiss Alps: Results of NRP 20*; Birkhäuser: Basel, Switzerland, 1997; pp. 251–259.
60. Sogin spa. *DN DI 0018—Complesso Stocaggio Alta Attività, Relazione Descrittiva Generale*; Sogin spa: Roma, Italy, 2018.
61. Sogin spa. *DN GS 00304—Sintesi Delle Basi Teoriche e Delle Modalità Di Applicazione Dei Criteri per La Realizzazione Della CNAPI*; Sogin spa: Roma, Italy, 2020.
62. Sogin spa. *DN GS 00056—Procedura Operativa Sogin per La Realizzazione Della CNAPI*; Sogin spa: Roma, Italy, 2021.